# **UC Davis**

Guidelines

## Title

Pavement Preservation Studies Technical Advisory Guide: Summary

## Permalink

https://escholarship.org/uc/item/24j441g7

# Author

Jones, D.

# Publication Date 2007

# Pavement Preservation Studies Technical Advisory Guide: Summary

Author: D. Jones

Partnered Pavement Research Program (PPRC) Contract Strategic Plan Element 3.2.9: Development of Guidelines for Effective Maintenance Treatment Evaluation Test Sections

# **PREPARED FOR:**

California Department of Transportation Division of Research and Innovation Office of Roadway Research

# **PREPARED BY:**

University of California Pavement Research Center UC Davis, UC Berkeley





#### DOCUMENT RETRIEVAL PAGE

Title: Pavement Preservation Studies Technical Advisory Guide: Summary					
Author: D. Jones					
Prepared for:	FHWA No:	b	<b>Date</b> :		
Caltrans	S/CA/RI-2006/25		January 2007		
Strategic Plan No:	Client Reference	e No:	<b>Status:</b>		
3.2.9	SPE 3.2.9		Final		

#### Abstract:

This document provides guidelines for the establishment, monitoring and reporting of pavement preservation experiments in California. Information is provided in chapters covering:

- Management and responsibilities
- Project fundamentals
- Experiment work plan
- Site selection
- Experiment construction
- Experiment monitoring
- Forensic investigations
- Laboratory testing
- Data analysis, reports and implementation
- Data management and documentation
- Example experiment work plans, checklists and forms

The document aims to assist with achieving successful completion of experiments and implementation of the findings.

#### Keywords:

Pavement preservation, experiment evaluation

#### **Proposals for implementation:**

Follow protocol in all future pavement preservation and innovative product experiments. Update

as required.

#### **Related documents:**

Pavement Preservation Studies Technical Advisory Guide (UCPRC-GL-2005-01)

Signatures:

	J. Harvey		J. Harvey	M. Samadian
D. Jones	Technical	D. Spinner	Principal	Caltrans Contract
1 <sup>st</sup> Author	Review	Editor	Investigator	Manager

The contents of this report reflect the views of the authors who are responsible for the facts and accuracy of the data presented herein. The contents do not necessarily reflect the official views or policies of the State of California or the Federal Highway Administration. This report does not constitute a standard, specification, or regulation.

# DOCUMENT REVIEW AND IMPLEMENTATION STATUS

This document has been reviewed within the University of California Pavement Research Center, by the Caltrans Division of Research and Innovation, and by the Caltrans Division of Maintenance, Office of Pavement Preservation and its appointed reviewers.

The document can be used as a guide for the design, construction and assessment of pavement preservation experiments. The document is released as a draft for implementation for a period of 12 months, ending December 2007. Any comments or recommendations to improve the document, based on use during implementation, should be forwarded to the Chief of the Office of Pavement Preservation. A revised document, incorporating comments received, will be released in January 2008.

## **PROJECT OBJECTIVES**

The objective of this project is to improve the quality of data and analyses obtained from Pavement Preservation and Innovative Product Experiments in California, and promote statewide implementation of the findings of successful studies.

This objective will be met after completion of three tasks:

- 1. Prepare and discuss a draft table of contents for a detailed guideline on undertaking pavement preservation and innovative product experiments.
- 2. Prepare a detailed guideline.
- 3. Prepare a summarized "glove-box" version of the detailed guideline.

This document addresses Task No. 3.

# TABLE OF CONTENTS

LIST OI	F TABL	ES	vi
LIST OI	F FIGUF	RES	vi
PURPO	SE OF	THIS GUIDELINE	/ii
1.	INTRO	DUCTION	1
	1.1.	Background	1
	1.2.	Pavement Preservation Definitions	2
	1.3.	Key Activities	3
	1.4.	Typical Pavement Preservation Activities	3
	1.5.	Quality Management	5
	1.6.	Using this Summary Guideline	5
2.	MANA	GEMENT AND RESPONSIBILITIES	7
3.	PROJE	ECT FUNDAMENTALS	9
4.	EXPEF	IMENT WORK PLAN 1	3
5.	SITE S	ELECTION1	5
6.	EXPEF	RIMENT CONSTRUCTION 1	9
7.	EXPEF	RIMENT MONITORING	23
8.	FORE	SIC INVESTIGATIONS	31
9.	LABOF	RATORY TESTING	33
10.	DATA	ANALYSIS, REPORTS AND IMPLEMENTATION	35
11.	DATA	MANAGEMENT AND DOCUMENTATION	37
12.	BIBLIC	OGRAPHY	39
APPEN	DIX A:	CHECKLISTS	11
APPEN	DIX B:	DATA COLLECTION FORMS	57

# LIST OF TABLES

Table 1.1:	Pavement preservation purpose	. 3
Table 1.2:	Typical pavement preservation activities	. 5
Table 7.1:	General description of extent classifications	25
Table 7.2:	Examples of physical measurements	29
Table 8.1:	Guide for forensic investigations	31

# **LIST OF FIGURES**

Figure 1.1:	Components of pavement preservation	1
Figure 1.2:	Flowchart of key activities	4
Figure 3.1:	Flowchart for project approval	10
Figure 4.1:	Flowchart for development of an experiment work plan	13
Figure 5.1:	Flowchart for site selection	16
Figure 6.1:	Flowchart for experiment construction	20
Figure 7.1:	Flowchart for experiment monitoring	23
Figure 7.2:	Flow diagram – five-point classification system	25
Figure 7.3:	Diagrammatical illustration of extent	26
Figure 8.1:	Flowchart for forensic investigations	32

# PURPOSE OF THIS GUIDELINE

This guideline has been written to assist Caltrans staff with establishing and monitoring pavement preservation experiments. Experience has shown that, although numerous such experiments have been built in the past, very little useful information that can be used to make informed decisions about implementing the treatment, technology, procedure, or product state-wide results. There are a number of reasons for this including movement and turnover of staff, inappropriate experimental designs, insufficient data collection and/or loss of interest over time (i.e., experiment is never completed). Considerable time and expense are incurred during the establishment of experiments. Failure to complete an experiment invariably means that it will be repeated by someone else, somewhere else at a later date. The same applies to experiments that although completed, are not coordinated at state level.

This summary guideline, which should be read in conjunction with the detailed guideline, provides direction on the following:

- Establishing a study team and assigning responsibilities
- Justification for doing an experiment
- Developing an experiment work plan
- Locating, marking out and establishing the site
- Construction of the experiment
- Monitoring the experiment
- Data analysis
- Reporting and implementation
- Data management

By applying the principles discussed in the guideline, the following can be achieved:

- Statistically valid, scientifically correct and defendable answers obtained within a determined time period
- Results from every experiment established, regardless of the movement of individuals within and out of the organization
- Findings that are applicable state-wide and useable by individuals outside the study
- Justification for expenses incurred
- Justification for statewide implementation
- Justification for changes to specifications and practices
- Accountability of individuals involved
- Prevention of duplication of effort



# 1. INTRODUCTION

#### 1.1. Background

Pavement preservation represents a proactive approach in maintaining highways. It enables State Departments of Transportation (DoTs) to reduce costly, timeconsuming rehabilitation and reconstruction projects and the associated traffic disruptions. With timely preservation the traveling public can be provided with improved safety and mobility, reduced congestion, and smoother, longer lasting pavements.

A Pavement Preservation program consists primarily of three components (Figure 1.1):

- Preventive maintenance
- Minor rehabilitation (non-structural)
- Routine maintenance activities



Figure 1.1: Components of pavement preservation

Caltrans invests millions of dollars each year in pavement preservation activities. Documented performance of the pavement preservation practices during these activities is important so that Caltrans can determine which alternatives are most appropriate under particular circumstances. Many factors contribute to this decision. To establish the most appropriate pavement preservation practice or to assess the performance and effectiveness of new materials or equipment, experiments are usually constructed and monitored. Provided that an appropriate experimental design is followed, the experiment is monitored regularly and objectively and the data is suitably interpreted, these experiments can contribute significantly to the understanding of pavement preservation and the state-wide implementation/ adoption of the most appropriate and cost-effective practices.



MTAG



Crack seal



Shoulder fog seal



Diamond grinding



The purpose of this document is to provide Caltrans personnel with guidelines for the consistent design, construction, and monitoring of experimental sections, capturing and storing data, and interpreting and documenting the results.

Obtained     Obtained       Optimized     Obtained       Davaement Preservation Studies       Davaement Advisory Guide       Dechnical Advisory Guide       Unter Unter
Darward 2007 Cudether: UPURC CL 2006 of <b>Darbarent Preservation Studies</b> <b>Technical Advisory Guide</b> Merrier Darbarent Preservations Studies Merrier Classes (Classes) Merrier Clas
Cuidem: UCRC.GL.20091 Database: UCRC.GL.20091 Database: UCRC.GL.20091 Database: UCRC.GL.20091 Database: UCRC.GL.20091 Autor: D.2009 Database: UCRC.GL.20091 Database: UCRC.GL.20091 Database
Parement Preservation Studies Technical Advisory Guide Advisory Guide Advisory Guide Advisory Constitution Designed Constitution States (States 128 Designed Constitution) Presented on Constitution States (States 128 Designed Constitution) Presented For Constitution States (States 128 Designed Constitution)
Answennen Presservation Studies Dechnical Advisory Guide 
Adversion Processing Adversaria Studies     Technical Advisory Guide     Arther: D. Jones     Market of Constraints     Adverse of Constraints     Adverse of Constraints     Adverse of Constraints     Adverse of Constraints     Presence of Constraints     Adverse of Constraints     Adv
Technical Advisory Guide Autor: D Jones Partner Research Pages (PPC) Contact Strange Plan Exercise Sectors Presented For Contact Strange Plan Exercise Presented For Contact Strange Plan Exercise Presented Proceedings (Plan Exercise) Presented Proceedings (Plan
Author: D Jones Purspeer / Australianti / Author: D Jones Destgeer / Guarden kr (Encl Multicianti Haufmeil Gualation Teal Sectors PREPARED POR: Oddess Department / Travention Oddess Department / Travention
Author: D Johnes Partnersk Research Regars (1940) October Staate (Staate 12.8 Destagement of Classifiers in Statistics Section PREPARED FOR: October Department of Travention Control Research and Statistics
Author: D Jones Destroyed Process Register (PFG), concert Lange Rev Learning of the Destroyed of Caladree for Calago, Multimeter Transmission Transmission Sectors PERSANCE (PCR) Concert Sectors Calago, Sector Calago,
Author: D Jones Pannend Neuronard Regard (PPA) Contrast Strading: Pain Beneral 2.02 Designent of Caladree in Stradie Automation Inselficient Caladian Trail PREPARED POR: PREPARED POR: Caladias Beneral 2.02 Designed and the Stradies and the Stra
Author: D Jones Purtupent Research Registin (PRC), Contra Strange, Plan Exercise Destagement of Causives in (Section Workstream) PREPARED FOR: Clinical Section Section (Section Section S
Partners Present Baseco Program (PPC), control Statiger Pan Gaussian Tel Development of Gaussiane to Effective Molecenson Treatment Databation Tel Scatoria PRESARED FOR: Calcular Danaman A Transmission Calcular Danaman A T
Pathward Revenuet Rev
Automatic assessed Research Research Program (Prevolutional catalog) Mith EMBIN(22): Development of Guidelines for Efficient Mainformation Treatment Equation Treat Construct PREPARED FOR: PREPARED FOR: Development of Transcription Development of Section Research and Interview Research Treatment Resea
PREPARED FOR: PREPARED BY: California Department of Transportation Division of Research and Increases Office of Research and Increases Division (Presearch Center ULC Direct), UD Berkeley
California Department of Transportation University of California Division of Research and Incovation Provement Research California UCD Davis, UC Benshim, UCD Davis, UC Benshim,
Office of Roadway Research UC Davis, UC Berkeley
57 UCPRC
Caltrans Devices of California Network Restance
January 2007
Guideline: UCPRC-GL-2005-02
Pavement Preservation Studies
Technical Advisory Guide:
Summary
Summary Autor: D Jones Proteed Person Program Program Program 12.07
Summary Autor: Durner Autor: Durner Partners/Partner/Souther Partners/Souther Test Development of Statistics of Souther Test Development of Statistics of Souther Test Development of Statistics of Souther Test Development of Southers of Souther Test Development of Southers of Southers Test Development of Southers of Southers Test Development of Southers Test Deve

UCPRC

However, in many instances, the purpose of the experiment is not clearly defined, accepted monitoring standards are not adhered to, data are not effectively captured, and the experiment is not completed with a result on which a decision can be made with regard to state-wide implementation. Alternatively, the originator of the experiment moves and his/her successor may not be aware or may not be willing to sustain the exercise. Consequently, inconclusive results are often obtained and the new procedure or practice is not adopted. Invariably, the experiment is repeated elsewhere by another individual, often with the same inconclusive result.

The purpose of this document is to provide Caltrans personnel with guidelines for the consistent design, construction and monitoring of experimental sections, capturing and storing data and interpreting and documenting the results. This guideline supplements the "Maintenance Technical Advisory Guide (MTAG)" and the "Guide to the Investigation and Remediation of Distress in Flexible Pavements" and uses information from those documents as well as past test section project evaluations located throughout the State of California.

The document is presented in two parts:

- A comprehensive document providing detailed information on establishing and monitoring pavement preservation test sections.
- A summary guide in the form of brief descriptions and checklists on key components of establishing and monitoring pavement preservation test sections (this document).

#### 1.2. Pavement Preservation Definitions

The distinctive characteristics of pavement preservation activities compared to construction, rehabilitation and emergency maintenance are that they restore the function of the existing roadway system and extend its service life, but do not increase capacity or strength (Table 1.1). Different pavement preservation terminology is often used by local and State DoTs. This can cause inconsistency relating to how preservation programs are applied and their effectiveness measured. To overcome these inconsistencies, the Federal Highway Administration (FHWA) has proposed a number of definitions (*FHWA Memorandum on Pavement Preservation Definitions, 09/12/05*).

Cotogory	Activity	Purpose			
Category	Activity	Increase capacity	Increase strength	Reduce aging	Restore serviceability
Construction	New construction Reconstruction	× •	<b>&gt; &gt;</b>	<b>√</b> √	✓ ✓
Rehabilitation	Major rehabilitation Structural overlay		~ ~	~ ~	✓ ✓
Pavement Preservation	Minor rehabilitation Preventive maintenance Routine maintenance			~ ~	✓ ✓ ✓
Maintenance	Reactive maintenance Catastrophic maintenance				✓ ✓

#### Table 1.1: Pavement preservation purpose

#### 1.3. Key Activities

The design, construction, monitoring and reporting of experimental sections can be divided into a number of key activities, all of which are equally important in ensuring that relevant data are captured and interpreted in such away that an informed decision can be taken on the implementation of the findings of an experiment. These activities include:

- Delegating responsibility
- Preparing an experimental design
- Selecting and establishing a suitable site
- Construction
- Monitoring
- Forensic studies
- Laboratory testing
- Data management
- Reporting and implementation

A flow chart of the process is provided in Figure 1.2. Each activity is discussed in the following chapters.

#### 1.4. Typical Pavement Preservation Activities

Various pavement preservation activities are performed on highways. Certain activities are preventive in that they are performed before any significant distress has occurred. Others are remedial and are carried out to repair distresses in the pavement.



Reconstruction



Rehabilitation



Preventive maintenance



Routine maintenance



Reactive maintenance



Catastrophic maintenance



Dowel bar retrofit



Chip sealing



Microsurfacings



Slurry sealing



Figure 1.2: Flowchart of key activities

Many routine activities are unlikely to be assessed in research experiments and will not be covered in any detail in this document. Typical activities that may well be researched are listed in Table 1.2. The list is not exhaustive and only provides an example of activities commonly investigated in pavement preservation experiments. The list does include issues such as drainage, pavement markings, barriers, water crossings and vegetation control, although investigations can be undertaken on these with a view to improving techniques or assessing new products. Throughout this document, where appropriate, activities will be referred to as 'total' and 'selective' treatments as detailed in the table.

Activity*	Area treated	Preventive	Remedial		
Addivity	Area treated	Treventive	Hemediai		
Thin overlays		$\checkmark$	$\checkmark$		
Ultra-thin overlays		$\checkmark$	$\checkmark$		
Bonded wearing course		$\checkmark$	$\checkmark$		
Microsurfacings	Total	$\checkmark$	✓		
Chip seals		$\checkmark$	✓		
Slurry seals		<b>√</b>	$\checkmark$		
Fog seals		$\checkmark$	-		
Crack seal		-	~		
Crack fill		-	$\checkmark$		
Joint seal		-	$\checkmark$		
Patching		-	✓		
Partial-depth concrete repair	Selective	-	✓		
Full-depth concrete repair		-	~		
Edge repair		-	~		
Diamond grinding		-	✓		
Dowel bar retrofit		$\checkmark$	-		
* Activities may include the u	se of mechanica	l improvements su	ch as		
geotextiles or geogrids					

#### Table 1.2: Typical pavement preservation activities

#### 1.5. Quality Management

The Caltrans Project Delivery Quality Management Plan (QM) was established to implement and document a fully integrated project delivery "Quality System" for all transportation projects regardless of funding source, sponsorship, or who performs the work. This plan focuses on the delivery of Quality Transportation Projects, emphasizing accountability and utilizing continuous improvements, to assist the Department in achieving its mission to "Improve mobility across California". In terms of pavement preservation experiments, quality management will aim to ensure consistently designed and tested experiments that provide good quality data that can be used with confidence to develop and implement procedures to improve delivery of infrastructure in California.

#### 1.6. Using this Summary Guideline

As the name implies, this document is a summary of a significantly more comprehensive guide on the design, construction, monitoring, and analysis of pavement preservation experiments. This summary guide provides an introduction to each chapter discussed in the more comprehensive guide, and highlights key points. More detail is provided on the site selection, construction and monitoring phases, where it is anticipated that the summary guide will be most used. The evaluator is, however, encouraged to regularly refer to the comprehensive guide





for more detailed information and discussion during each phase of an experiment, specifically with regard to quality management.

This summary guide includes the example checklists and forms contained in the comprehensive guide.

# 2. MANAGEMENT AND RESPONSIBILITIES

A team of suitably qualified and experienced personnel is required to manage, establish and evaluate pavement preservation experiments in close liaison with other units who have responsibility for the road. This team will be accountable for optimizing the establishment and evaluation of pavement preservation experiments and presentation of the highest quality data possible in a format that is useable by other Divisions within Caltrans. The establishment and evaluation of experiments is expensive. Outcomes may result in state-wide changes to current practice and specifications and implementation might be scrutinized by many individuals within the state, as well as nationally and internationally. Roles and responsibilities thus need to be clearly defined and monitored by means of appropriate job descriptions, key-result areas, and performance evaluation.



Typical **staffing requirements** associated with pavement preservation experiments include the following. Roles and responsibilities for each are explained in the detailed guideline.

- Project Champion
- Project Engineer/Project Manager
- Database Manager
- Instrumentation Technician
- Evaluation Team



Typical staff organization chart for pavement preservation experiments





# 3. PROJECT FUNDAMENTALS

Project fundamentals revolve around the need to do the experiment and the implications of implementing the findings. Pavement preservation experiments are built for a variety of reasons, primarily to understand the behavior, performance, and potential benefits of doing something new or differently. However, experience has shown that in many instances, the objectives for constructing an experiment are often not fully thought out, insufficient background study is carried out, inappropriate data is collected, monitoring programs and protocols are not adhered to, the results are not written up, and the findings are not implemented. Therefore, it is imperative that the reason for initiating the experiment is fully understood and that a comprehensive experimental design is prepared in order to ensure that the objectives are met and, if successful, the procedure being evaluated can be adopted as standard practice, where appropriate, with confidence.



In the detailed guideline, this chapter explains:

- Study proposals (Checklists 1 and 2, Appendix A)
- Background studies
- Introduction to experimental designs (Checklist 3, Appendix A)

A flow chart depicting the processes covered in this chapter is provided in Figure 3.1.

**Study proposals** for experiments are considered in two phases by Caltrans — pre-proposal and full proposal. A summary of the process proposed by Caltrans Division of Maintenance, Office of Pavement Preservation is provided in the detailed guide. Further information can be obtained from the Chief of the Office of Pavement Preservation.

**Background studies** check what work has already been done on the topic and help to decide whether the experiment is required. Information can be sought on similar experiments and the key parameters that need to be assessed. A brief state-of-the-art report should be prepared on completion of the background study summarizing:

 Overview of why the study is being undertaken and the potential benefits to Caltrans





#### Figure 3.1: Flowchart for project approval

- Findings of the literature review
- Results from the preliminary laboratory study if undertaken
- Applicability of the findings to California
- Justification to continue or discontinue the study
- Proposed experimental design

A **full proposal** should be prepared after completion of the background study. This proposal should include the content from the pre-proposal and background information documents, as well as:

• Potential partners (those who have a vested interest in the results and who could make technical, financial or "in-kind" contributions)



- Project logistics
- Proposed work plan (see Chapter 4) and timetable
- Estimated study budget
- Definition of success, including the performance and cost criteria that will define success compared to current Caltrans practice.
- Details on how the findings would be implemented including expected deliverables, who would lead the implementation process and probable timetable and cost
- Signed commitment by the project team to complete the study

#### \*\*\*\*\*\*\*

**Pavement preservation experiments** can take many forms, including but not limited to one or a combination of the following:

- Assessing a new strategy/treatment/technology (i.e., does this technology "work"?)
- Comparing one strategy/treatment/technology with another (i.e., which is the "best" treatment?)
- Refining a strategy/treatment/technology (i.e., what is the "best way" to do this treatment?)
- Understanding a treatment/technology (i.e., "how" does this technology work?)

**Replicate studies** are important in many types of experiment, especially where variables (construction, material variability, weather) can influence performance of the treatment being assessed. The inclusion of replicates will improve the reliability of the findings. Two types of replicate need to be considered:

- Replications within the same test section, typically used to deal with construction, material, and/or pavement variability within the test section.
- Replications between other regions, materials, pavement types, climates and/or traffic, etc. in the state to identify boundaries to implementation, if these are not already being considered as factors in the experimental design.

Key **evaluation criteria**, on which the success of the treatment will be decided, need to be established for each experiment. These should be linked to the experiment objective. For example, if two modified binders are being compared in a chip seal experiment, the key evaluation criteria will probably be





Heavy Vehicle Simulator experiment - "how does this technology work"



Rut evaluation



raveling/stone loss over time. Evaluation criteria are discussed in more detail in Chapter 7.

In any experiment, it is important to establish and understand what the **failure criteria** for any experiment are and what action needs to be taken when failure occurs. Examples of failure criteria include rut depth, stone loss, and length or area of cracking.

Failure criteria - bleeding

The criteria for deciding when an **experiment is completed** should also be determined in the experimental design. This will be the point at which sufficient data has been collected such that an informed decision can be made on whether to adopt/proceed with implementation or reject the strategy/ treatment/technology. It could be time (e.g., level of performance after a period of elapsed time) or performance based (e.g., no improvement over control in terms of performance indicators).

# 4. EXPERIMENT WORK PLAN

The Experiment Work Plan is a comprehensive document detailing the objectives of the experiment, the experimental design, the control, evaluation procedures and responsible persons. It should be considered a "live" document in that changes during the course of the experiment are often necessitated. An Experiment Work Plan must be prepared for every experiment once the decision to proceed with an experiment is made by the Project Champion and Pavement Preservation Task Group Chair after completion and review of the background study and detailed proposals.

The procedure for preparing an experiment work plan, the work plan content and format and revisions to the work plan are discussed step-by-step in the detailed guide. Checklists 4 to 6 in Appendix A are relevant to procedures in this chapter. A flow chart summarizing the process is provided below (Figure 4.1).





#### Figure 4.1: Flowchart for development of an experiment work plan



# 5. SITE SELECTION

Site selection is critical. The site needs to be representative of roads, traffic and environment where the pavement preservation strategy might be used if proved successful in the proposed experiment. If feasible, experiments can be combined to optimize monitoring schedules and comparisons between ongoing performances of the different studies. All experiments should include a control section and replicates. Control sections are typically the standard pavement preservation strategy that would have been used. For example, if a new chip seal design is being assessed, the experiment should include a section constructed using the existing chip seal design so that a direct comparison of performance can be made. Replicates are typically included to assess variability at each site and the influence of, for example, climate and traffic between sites.

In the detailed guide, this chapter discusses the following components of site selection. A flow chart depicting the processes covered is provided in Figure 5.1.

- Site selection procedure (Checklists 7 and 8 in Appendix A)
- Experiment numbering
- Layout and marking (Checklist 9 in Appendix A)
- Instrument installation

The identification and selection of experiment sections will depend on the specific criteria and objectives of the study. The following general issues should, however, be considered when selecting sections:

- Sections should be representative of the issue being investigated and results obtained from these sections should be representative of other roads with similar conditions.
- Where possible experiments should be conveniently located for monitoring and or demonstration purposes.
- Individual sections within the experiment, including the control, should be similar in terms of alignment, structure, traffic, and condition. Sideby-side sections should not be used for direct comparison.
- The establishment of the section should not pose a safety hazard to road users, or be positioned so that the safety of the persons monitoring the section is jeopardized.



Road is curved, sight distance is limited, and structure is inconsistent.



Road is straight, safe, and consistent.



FWD



Consistent cracking



Consistent bleeding/stone loss



Inconsistent rutting and cracking



Inconsistent concrete surface



Environmentally sensitive

- The road on which the section is being located should not be maintained, rehabilitated or resealed within the planned monitoring period, unless assessment of that intervention is part of the monitoring program and prior warning is given to the Project Engineer.
- Sections should be located as close as possible to traffic counting/weighin-motion stations, unless a station is incorporated into the section.
- Sections should be selected such that testing to "failure" of certain sections can be completed and then repaired without significant impacts to the road user.



Figure 5.1: Flowchart for site selection

#### The site selection procedure involves three main stages:

- Desktop study
- Site visit
  - o Experimental design considerations
  - o Safety considerations
  - o Environmental considerations
- Site report and approval

Each experiment, and section within the experiment if applicable, should be assigned a **unique experiment number** for management purposes. A number should be obtained from the Chief of the Office of Pavement Preservation. This number will be linked to the proposal and experiment specification registers described in the previous chapter.

Once selected the test sections should be **labeled**, **marked and instrumented** according to the requirements of the Experiment Work Plan. Suitable signs should be erected at either end of the experiment with experiment details and a contact number or website where Caltrans staff can obtain additional information and notify the Project Engineer of any observations or interventions that may be necessary. The length of the experiment will be detailed in the Experiment Work Plan and will vary depending on the treatment being assessed. Typical sections lengths are:

- Total surface 200 m (600ft)
- Selective surface sufficient length to have at least 12 replicates with the same treatment (i.e., 12 cracks, 12 potholes, 12 joints)

# PPTS/3/05/1/1

Example experiment section number



Experiment number sign



# 6. EXPERIMENT CONSTRUCTION

The performance of any road is directly related to the quality of construction. It is therefore imperative that the construction process is closely observed so later performance can be related back to it. Since pavement preservation strategies are being evaluated, it is also very important that the road is comprehensively evaluated before any work is undertaken in order to determine the level of success of the strategy.

When undertaking any assessments, observations or measurements, it should always be kept in mind that the data will ultimately be used in an analysis to determine the effectiveness of the technique and/or product being assessed. Careful consideration should thus be given to the manner in which the assessments are recorded such that quality analysis can be undertaken and valid conclusions drawn.

In the detailed guide, this chapter discusses the following components of experiment construction. A flow chart depicting the processes covered is provided in Figure 6.1.

- Pre-construction assessment (Checklist 10 in Appendix A)
- Construction assessment (Checklist 11 in Appendix A)
- Material sampling
- Instrument installation

Typical issues to consider in the **pre-construction assessment** are listed on Checklist 10 in Appendix A.

Every aspect of the **construction process**, from preparation of the surface through cleaning up excess materials (e.g., brooming after chip seal application) can influence later performance of the treatment. The entire process thus needs to be observed and systematically documented so later performance can be linked to the construction process where applicable. Examples of critical areas requiring observation include, but are not limited to:

- Calibration of the spray and stone application rate on fog seals and chip seals
- Brooming of excess stone after chip seal application
- Repair of distress prior to overlay treatments



Structural assessment prior to action



Poor drainage may influence experiment performance



Microsurfacing application



Chip spreader calibration



Brooming excess chip seal stone



- Checking binder temperature and compaction techniques
- · Cleaning process and effectiveness in crack, joint and pothole repairs
- Reviewing quality control and quality assurance procedures



Figure 6.1: Flowchart for experiment construction

If a **proprietary treatment** is being assessed, then the manufacturer or supplier should appoint a technical representative to provide advice on the project. They should also provide a step-by-step procedure together with checklists that need to be followed in order to ensure that the experiment is constructed correctly. The procedure must clearly state situations to avoid and the consequences if they are not.

The Caltrans Project Engineer must supervise and systematically document the entire **construction process** from site preparation through to opening the road to traffic. If applicable, any deviations from procedures for proprietary products should be noted. On completion, the Project Engineer must be fully satisfied that the test section is representative of the Experiment Work Plan and that sufficient data have been collected from the construction process to adequately relate later performance to the road prior to treatment, and to construction.

Typical issues to consider when observing construction include, but are not limited to (see Checklist 11 in Appendix A):

- Systematic documentation of the process and deviations from the procedure provided
- Treatment (e.g., binder, aggregate, sealant) source and characteristics
- Equipment type and condition
- Calibration procedures
- Surface, crack or pothole preparation
- Compaction
- Establishment, application and demobilization time
- Quality control and quality assurance processes followed
- Uniformity
- Wastage
- Problems encountered and how they were dealt with
- Recommendations to improve the process

All observations should be documented on a Construction Assessment Form. The contents of the form will depend on the type of treatment. An example of a form is provided in Appendix B (Form 1). A checklist, relevant to the pavement preservation treatment, should be completed to ensure that all aspects of the construction process have been documented and recorded.

A **quantitative measure** is always more useful than a subjective observation when analyzing data collected from an experiment. Where feasible, any component of the process being assessed that can be measured should be measured with appropriate calibrated equipment and the data recorded. Typical parameters that can be measured during construction include, but are not limited to:

- Haul distances and times
- Time taken for each component including opening and closing times
- Characteristics of the surface before and after treatment:
- Air and surface temperatures and other site weather conditions
- For overlays:
  - o Asphalt concrete temperature
  - o Thickness
  - Quantity applied per unit surface area
  - Compaction procedures





Thickness control



Contamination







Drainage impairment



Measurement of early rutting



Aggregate samples



Density after compaction



Slab sample



Core sample

- For seals:
  - o Binder temperature
  - o Spray rate
  - o Aggregate size, shape and quantity applied per unit area
- For patches:
  - o Thickness
  - o Quantity applied per unit surface area
- For cracks
  - Sealant temperature
  - Sealant applied per linear meter
- Density after compaction

Copies of the Resident Engineer's and Inspector's notebooks should be obtained where possible.

**Representative samples** of all the materials used in the pavement preservation treatment should be collected at appropriate times throughout the construction procedure. Quantities and replicates will depend on the tests detailed in the Experiment Work Plan. A sample log should be kept and records of all samples should be noted on the Construction Assessment Form. All samples should be appropriately labeled. Two types of sample may be collected, namely for:

- Laboratory testing
- Reference purposes

A **construction report** should be prepared summarizing the construction process and detailing any specific issues that may influence performance and how these should be assessed during later monitoring evaluations. Deviations from the Experiment Work Plan should be listed. The report should also clearly state whether procedures were such that a satisfactory experiment has been constructed and that monitoring should continue. The as-built records should be included in the report and will serve as a basis for later monitoring. Report approval signifies that monitoring of the experiment can continue.

# 7. EXPERIMENT MONITORING

Experiment monitoring is the phase during which most of the data that will be used in the analysis is collected. Experience has shown that it is also the phase when studies lose momentum and are even abandoned as new interests are followed and/or staff move on to other activities, positions or employment. It is thus important to maintain interest in experiments and ensure that the monitoring program is adhered to. Movement of staff should not affect successful completion of a study.

In the detailed guide, this chapter discusses (Figure 7.1):

- Background information on experiment monitoring
- Operational issues (Checklist 12 in Appendix A)
- Monitoring timetables
- Protocols and criteria
- Visual assessment procedures (Checklist 13 in Appendix A)
- Measurements and sampling



Figure 7.1: Flowchart for experiment monitoring

Visual assessment of rutting



Longitudinal crack



Fatigue crack, base failure



Shear crack, base failure



Pumping through crack



Pumping through patch joint

The appearance of distress is varied and often extremely complex. The task of describing this is achieved by recording its main characteristics - the so-called attributes of distress. The attributes typically used in assessment are type, degree and extent. Detailed explanations relevant to each type of distress are described in the Pavement Condition Survey Manual and similar appropriate visual assessment guides.

<u>Type of Distress</u> - The type of distress evaluated will depend on the purpose of carrying out the assessment. For example, types assessed on chip seal overlays will differ from those on joint seal experiments. A number of assessment parameters are considered essential for any type of evaluation, while detailed descriptions of particular distress types will be required for specific pavement preservation treatments. Typical parameters assessed include, but are not limited to:

- Cracking (fatigue, block, edge, longitudinal, reflection, transverse, corner, durability)
- Potholes and/or existing patching and patch deterioration
- Surface deformation (rutting, shoving)
- Surface defects (bleeding, polished aggregate, raveling, map cracking, scaling, popouts)
- Miscellaneous distresses (lane-to-shoulder drop-off, lane-to-shoulder separation, water bleeding and pumping, blowouts)
- Joint deficiencies (joint seal damage, spalling, faulting)
- Functional performance (ride quality, skid resistance, spray, noise, etc)

Distresses can be assessed individually or in terms of their interactive effect on the functional performance of the road together with deflection, material properties, road profile (transverse and longitudinal), drainage, etc. An example of this is the development of potholes, which result in deterioration of overall functionality, particularly riding quality.

<u>Degree</u> - The degree of a particular type of distress is a measure of its severity. Because the degree of distress can vary over the pavement section, the degree to be recorded should, in connection with the extent of occurrence, give the predominant severity of a particular type of distress. The degree is described by a number where:

• Degree 1 indicates the first evidence of a particular type of distress ("slight").

- Degree 3 indicates a warning condition. This would normally indicate that intervention might be required in order to avoid the distress deteriorating to a severe condition.
- Degree 5 indicates the worst degree ("severe"). Urgent attention is required.

Degree descriptions relate to the possible consequences of each type of distress and therefore also to the urgency of maintenance or rehabilitation. A flow diagram illustrating the use of the five-point classification system is shown in Figure 7.2.





Degree 1 distress



Degree 3 distress



Degree 5 distress

Figure 7.2: Flow diagram – five-point classification system

<u>Extent</u> - The extent of distress is a measure of how widespread the distress is over the length of the experimental section or panel. The extent is also indicated on a five-point scale in which the length of road affected by the distress is estimated as a percentage. The general description of the extent classifications is given in Table 7.1 and illustrated diagrammatically in Figure 7.3.

Extent	Description	Estimate (%)
1	Isolated occurrence, not representative of the section or panel being evaluated.	< 5
2	Between 1 and 3	5 - 20
3	Intermittent occurrence, over most of the section or panel or extensive occurrence over a limited portion of the section.	20 - 60
4	Between 3 and 5	60 - 80
5	Extensive occurrence.	80 - 100

 Table 7.1: General description of extent classifications


Extent = 5: extensive occurrence

```
+
 +
    +
             +
                +
                        +
                           +
                               ++
                                   +
                                      +
                                         + + + +
                                                ++
                                                       +
                                                          +
                   + + +
                           +++ +
+ + +
               +
                                        + + ++ ++
                                                      + + +
```



#### Figure 7.3: Diagrammatical illustration of extent

Depending on the study, the maximum severity possible is often of equal or greater interest than the predominant severity. In terms of pavement preservation test sections, specific interest will be on those defects that the treatment was intended to address.

To minimize the element of subjectivity and to ensure good knowledge of the assessment procedures, it is essential to **train and calibrate** all evaluators at regular intervals.



Safety considerations

There are numerous **operational issues** that need to be taken care of prior to undertaking a monitoring evaluation, including notifications, traffic closures and equipment preparation. These will differ between Districts and between experiments and are not covered in detail in this guideline. An example checklist (Checklist 12) is provided in Appendix A. The **monitoring timetable** will be detailed in the Experiment Work Plan. When preparing this timetable, it is important to have a balance between collecting sufficient data and collecting too much. It is also important to identify an expected end point for the experiment, either linked to:

- Time (e.g., exceeds expected design life in years),
- Traffic (e.g., cumulative vehicles passed or exceeds expected design life in axles), or
- Failure criteria (e.g., rut depth).

The **protocols and criteria** that need to be used as a basis for monitoring will be detailed in the Experiment Work Plan. Visual assessments will typically be carried out using the Caltrans Visual Condition Survey Manual. If more detail is required for analysis purposes, the LTPP Distress Identification Manual can be used. Caltrans or ASTM methods should be followed for measuring functional parameters such as ride quality, skid resistance, splash and spray, and noise.

It is important to establish and understand what the **failure criteria** for any experiment are and what action needs to be taken when failure occurs. Examples of failure criteria, based on California requirements, that can be used in assessing pavement preservation experiments include, but are not limited to:

- Chip seals and overlays
  - $\circ$  Crack severity and extent [e.g., >2.5 m (6.5 ft) total length or 2.5 m/m<sup>2</sup> (6.5 ft<sup>2</sup>) total crack density]
  - Rut depth [e.g., > 12.5 mm (0.5 in.)]
  - $\circ$  Stone loss (e.g., > 20% of area)
- Reinforcement materials
  - Reflective cracking [e.g., >2.5 m/m<sup>2</sup> (6.5 ft) total crack density,
     >3 mm (0.1 in.) width]
  - Rut depth [e.g., >25 mm (1.0 in.)]
- Crack and joint sealants
  - Spalling [e.g., >100 mm (4 in.) wide]
  - Separation and/or shrinkage [>3 mm (0.1 in.)]
  - Whip off [>25 mm (1.0 in.)]
- Pothole repair materials
  - Deformation [e.g., >25 mm (1.0 in.)]
  - Cracking (e.g., > 10% of area)
  - Separation and/or shrinkage [e.g., >3 mm (0.1 in.)]
  - Punch outs (any)



FHWA LTPP distress identification manual



Failed chip seal (>20% stone loss)



Patch joint failure



Skid resistance and permeability measurements



Visual assessments

VISUA	L A	SE	SSM	ENI	FO	RM-	FL	XE	LEI	PAV	EME	NTS		For	12
Section No	-	Location Date Evaluator						Evaluator							
	Surfacing assessment						Panel	· · ·							
Surfacing type	<u> </u>	-	_	-	_	-	_	-	_	-	_				
Textus	l vi	iŋln	9	F	Di	Т	F - 1		144	dlu	n	M-C	Course		
Volds	l Vi	inin	a l	Nk	ine i	+	Ν.	F		<b>N</b>	-	F. M	Many	-	
-		-	Deg	166					Dater	t					
	511	pht		_	801	ere	<5	_	_	_	-80	Langin	was	NUMBER	Panel
Mechanical failure	0	1	2	3	4	6	1	2	1.2	4	6				
Other taldie	10	1	2	3	4	•	1	2	3	4				_	
see and unsund	0	1	2	3	4	•	1	z	3	4		Narrow	Wide	Position	
Surface cracks	0	1	2	3	4	6	1	2	1.2	4	5				
Binder condition	0	1	2	3	4	•	1	2	3	4	5	ACEVA	8000	Position	
Aggregate loss	0	1	2	3	4	6	1	2	3	4	5				
	_		-		_	284	other	at as	00001	mid	it i				_
			100	160					2024	ĸ		rearrow	wide	. Position	Panel
	SAL	ght		Sev	000		<5		> 60	_	_	(%iarea)	(% area)		
Cracks- block	10	1	12	3	4	1.6	11	2	3	4	5		L		
Cracks- longitudinal	0	1	2	3	4	6	11	2	13	4	6				
Cracks transverse	0	1	2	3	4	6	1	2	5	4	6				
Cracks- crocodile	0	1	2	3	4	6	1	2	3	4	5				
Cracks- parabolic	0	1	2	3	4	e	1	2	3	4	6				
Funping	0	1	2	3	4	6	1	2	3	4	5				
Futting	0	1	2	3	4	6	1	2	3	4	5				
Undelation'settling	0	1	2	3	4	6	1	2	3	4	5				
Edgebreak	0	1	2	3	4	-6	1	2	3	4	5	Number	Diameter		
Pothokes	0	1	5	3	4	6	1	2	3	4	5				
Colombation	0	1	2	3	4	6	1	2	3	4	5				
					_	_						Small	Modium	Largo	Panel
Patchingidigouts	0	1	2	0	4	6	1	2	2	4	5				
	_				_	Fun	ctior	al a	<b>100</b> 00	sner	nt				
			ogre:		~ 1							file ricing t	lactors		
Fiding quality	11	2	13.1	41	5	Pot	top	T	I Pa	tch	TΤ	Undulatio		L oottoo	Bat
Skild registance	11	2	2	4	5	Die	bed	+	1 20	1sh	+ +				
Surface drainage	ti	2	3	4	5			-			-				
Side drainate	ΙŻ	х	-					-		-					
Noise		-	-	-				-		-			Pho	ice	
		_		_				_		_		-		_	_
		_		_				_		_		_			
	-	-	-	-	-	-	-	-	-	-	-				
		-		-				-		-					
	_	_	_	_	_	_	_	_	_	_	_	$\vdash$			
		_		_				_		_					
	_	-	_	-	_	_	_	-	_	-	_	i			_
		_		_				_		_					
Compared with previo	19.01	du	tion	2			Y			N					
						_		_		_	_				

Visual assessment form

Depending on the type of experiment, failure could also be determined by functional properties such as riding quality, skid resistance, spray and noise (e.g., exceeding specified limits). Once failure has occurred, the experiment can either be terminated or a maintenance intervention can be carried out and the monitoring continued if treatment life-cycles are being assessed.

**Visual assessments** should be carried out on each section or panel according to the criteria detailed in the Experiment Work Plan and using the protocols described above. Prior to each evaluation, the previous evaluation forms should be reviewed in order that the evaluator can familiarize him/herself, be able to identify new deterioration, and distinguish between deterioration that occurred prior to and after the previous monitoring visit. A systematic process should be followed such that the entire panel or section is covered and all parts of the evaluation form are completed. The road surface should be viewed from all angles (i.e., both ends and both sides) to ensure that the angle of sunlight and shadows does not influence the rating. The evaluation form should be logged to show that it was not overlooked. Digital photographs should also be taken during each visit and recorded on the evaluation form.

Observations and measurements should be recorded on the standard forms provided with the Pavement Condition Survey Manual, or a customized form prepared for the experiment (see example Forms 2 and 3 in Appendix B). If customized forms are prepared, the same form must be used for all monitoring to ensure consistency and to facilitate analysis.

The evaluator should also carry out a **first-level check** by comparing the previous evaluation with the current one. This is achieved by comparing forms and identifying any discrepancies such as decreasing rut depth or the presence of a specific distress in a previous evaluation and its absence in later evaluations. All discrepancies should be corrected or justified before completing the evaluation. If necessary, part of the evaluation may need to be repeated. A checklist (Checklist 13 in Appendix A) should be used by the evaluator as a reminder to ensure that all requirements are met.

**Quantitative measures** are always more useful than subjective observations when analyzing data collected from an experiment. Where feasible, any component of the process being assessed that can be physically measured should be measured with appropriate calibrated equipment and the data recorded, either on an appropriate form, or electronically depending on the parameter and the equipment used. Parameters that need to be measured during the visual assessment will differ depending on the type and objectives of the experiment. Some examples of physical measurements on different pavement preservation experiments are listed in Table 7.2.



FWD measurement



Profiler



Measurements on experiment



Rut measurements



DCP measurements

l able 7.2:	Examples	of physical	measurements
-	-		

Measurement	surface treatment	treatment	Method
Cracking • Fatigue • Block • Longitudinal • Reflection • Transverse • Corner • Durability Crack seal • Shrinkage		- - - - - -	Tape, wheel, digitized photo Tape, wheel Tape wheel Tape, wheel, digitized photo Tape, wheel Tape Tape, wheel Tape, steel ruler
Surface Deformation <ul> <li>Rutting</li> <li>Shoving</li> <li>Potholes</li> <li>Patch deterioration</li> <li>Patch shrinkage</li> <li>Patch deformation</li> </ul>	✓ ✓ - -	- - - - - - - - - - - - - - - - - - -	Straight edge & wedge Straight edge & wedge Straight edge & tape Straight edge & tape Tape measure, steel ruler Straight edge & wedge
Surface Defects <ul> <li>Bleeding</li> <li>Raveling/stone loss</li> <li>Scaling</li> <li>Popouts</li> </ul>	↓ ↓ ↓	√ √ - √	Tape, wheel Tape, wheel Tape, wheel Straight edge & tape
Miscellaneous <ul> <li>Blowouts</li> </ul>	~	~	Straight edge & tape
Joint Deficiencies <ul> <li>Seal shrinkage</li> <li>Faulting</li> </ul>	- √	√ √	Tape, steel ruler Tape, steel ruler
Functional • Longitudinal profile • Riding quality • Skid resistance • Noise • Spray	* * *	✓ ✓ ✓ –	Laser profilometer Laser profilometer Skid or Pendulum tester Noise tester Spray tester of photographs
Structural • Deflection • In situ strength • Modulus • Layer thickness		- - -	FWD DCP FWD, Seismic GPR



Forensic investigation

If a **failure** has occurred on a section, the cause should be identified and documented. A forensic investigation should be considered if the cause cannot be determined with confidence, for example, excessive stone loss on a chip seal, or rutting after the application of a fog seal.

The need to collect **samples** from a section will depend on the type and objectives of the experiment and will be detailed in the Experiment Work Plan. Samples should be correctly labeled and a sample log should be kept for any samples taken. All sample details should be recorded on the Assessment Form.

## 8. FORENSIC INVESTIGATIONS

Forensic investigations should be undertaken to confirm the mode of and reason for failure on any experiment. They should also be considered as a final opportunity to rigorously study the section, the findings of which could contribute significantly to understanding how the various treatments performed. Most forensic evaluations on pavement preservation treatments will simply involve a close-out evaluation. If the reason for failure cannot be determined with certainty, a more detailed forensic investigation by means of cores and/or test pits may be required.



Test pit and cores



Test pit



Test pit - note variable layer thickness



Core log

This chapter in the detailed guide covers (Figure 8.1):

- Level of detail
- Test pit location
- Coring
- Test pit excavation
- Sample logistics
- Test pit logging
- In-pit testing
- Test pit repair

A guide for the need for forensic evaluations in pavement preservation experiments is provided in Table 8.1.

Activity*	Detailed forensic required?	Test	Cores
		pit +	only
		cores	
Thin overlays	Yes, if rutting & cracking present	$\checkmark$	-
Ultra-thin overlays	Yes, if rutting & cracking present	$\checkmark$	-
Bonded wearing course	Dependent on failure mechanism	$\checkmark$	1
Microsurfacings	No, unless deformation after application	-	1
Chip seals	No, unless deformation after application	-	· ·
Slurry seals	No, unless deformation after application	-	
Fog seals	No, unless deformation after application	-	
		_	•
Crack seal	No	-	✓
Crack fill	No	-	$\checkmark$
Joint seal	No	-	$\checkmark$
Patching	Dependent on type of failure	$\checkmark$	$\checkmark$
Partial-depth PCC repair	No	-	✓
Full-depth concrete repair	Dependent on type of failure	✓	✓
Eage repair		_	
Diamono grinding			, ,
Dowel bar retrotit		-	· ·
		-	V

Table 8.1:	Guide f	or forensic	investigations
------------	---------	-------------	----------------







In pit density measurements



In pit DCP measurements



Test pit profile, note rutting in lower AC layer



Test pit profile





#### 9. LABORATORY TESTING

Laboratory testing is carried out in order to obtain an understanding of the material characteristics of the existing road surface or treatment being applied. In most instances these properties need to be known in order to understand why the road performed the way it did and to determine a set of criteria that can be used as a basis for determining where treatments or techniques that are being assessed can be applied elsewhere on the network.

Laboratory testing should only be carried out when the results will enhance knowledge of how the pavement performed and the reliability of the findings of the study in terms of addressing the study objectives. Testing should not be carried out simply for the sake of testing. The need for testing and the type of testing will be identified in the Experimental Work Plan.

Testing that might be carried out typically includes characterization of the properties, durability, and performance of the various materials used in the experiment, and samples removed during the course of the experiment or after completion of the experiment

A discussion on laboratory testing falls outside the scope of these guidelines. However, the following should be considered before testing:

- Care should be taken to fully understand a test, its purpose and its limitations before selecting it. Most tests are developed for a specific purpose. When used to test something outside the original scope, the mechanism and results may not be entirely relevant. Results need to be interpreted with care and the test may need to be modified to suit the need.
- An appropriate method may need to be sought to test a particular parameter. This may not be commonly used within Caltrans and laboratory staff may need to be trained in its use. Alternatively, a new test may need to be adopted or developed to address a particular need.
- Test methods should be strictly adhered to, unless modified to suit the needs of the experiment. If modified, the changes need to be clearly documented with a justification for doing so. Test methods should not be changed simply to obtain a satisfactory answer.



Indirect tensile (ITS) strength test

Laboratory testing procedures are fully documented in the California Test Methods document. Where appropriate, ASTM, AASHTO, and/or other organizations' test methods may be followed. The reasons for using an alternative test method should be justified.

#### 10. DATA ANALYSIS, REPORTS, AND IMPLEMENTATION

Appropriate data analysis and reporting is a fundamental part of any experiment. In this phase of the research, the data collected from the visual assessments and measurements is analyzed to determine whether the strategy, treatment, technology, procedure and/or product performed and behaved in a manner, such that adoption of it would have benefits over existing practice.

This chapter in the detailed guide covers:

- Data analysis
- · Construction, progress, and first- and second-level analysis reports
- Implementation

The focus of **data analysis** will be the systematic comparison of the behavior and performance of the strategy, treatment, technology, procedure or product against that of the control. The criteria that are used for this comparison will depend on the Experiment Work Plan.

**Reports** are the means by which experiments, findings and recommendations are documented. Format and content will depend on the type of experiment. Five types of report are typically prepared during the course of an experiment:

- Site selection reports
- Construction report
- Progress/interim reports
- Research reports
  - o First-level analysis report
  - o Second-level analysis report
- Implementation report

**Implementation reports** provide a summary of the experiment and the findings, together with recommendations on how the findings should be implemented. The report should be presented to the relevant office chiefs and disseminated to the district maintenance and materials engineers, and depending on the outcome, an implementation/adoption timetable should be agreed to.





**Implementation** of the findings is perhaps the most important, but often most overlooked, phase of any experiment. By following all the procedures discussed in these guidelines, valid and quantified justifications for implementing new or improved technologies and procedures can be developed. Once defined, these technologies and procedures need to be systematically implemented. The following implementation process is proposed:

- The project champion should notify relevant head office staff and district office maintenance and materials engineers about the experiment(s) in the early stages of the study. This notification can also be seen as an opportunity to identify potential replicate sections, and to find out about similar experiments that may have been conducted in the past, but not documented.
- The project engineer should send brief progress reports and updates via email to head office staff and district office maintenance and materials engineers throughout the duration of the study. If early significant findings are noted, engineers from other districts should be encouraged to visit the experiment as part of future monitoring exercises.
- On completion of the study, the summary/implementation report should be presented to the office chiefs at a Pavement Standards Team meeting. This exercise should be used to initiate the implementation plan proposed in the implementation report.
- Depending on the recommendations in the implementation report, proceed with implementation. This may include:
  - Revision of the Maintenance Technical Advisory Guide (MTAG)
  - Revision of standards, guideline documents, specifications and procedures
  - o Notifying relevant staff of the revised procedures
  - $\circ$   $\;$  Workshops and demonstration projects to disseminate the findings.

## 11. DATA MANAGEMENT AND DOCUMENTATION

A comprehensive record of data documenting the behavior of the test section and comparison to a control is critical to the success of any experiment. This requires a systematic data capture, storage, and retrieval procedure to ensure accuracy, uniformity and continuity in measurements.

This chapter in the detailed guideline discusses:

- The Project File
- Checklists
- Data collection forms
- Proposal register
- Experiment register
- Progress reports

A **project file** should be opened for each experiment when a proposal is prepared. All documentation relevant to the project should be kept in the file. The Project File "belongs" to an experiment and not to an individual and the contents should be accessible to any interested person.

**Checklists** are an effective way of ensuring that all relevant tasks for a particular part of a study are completed. They also provide a record to prove that the tasks were carried out and can also be used to guide the process.

**Data collection forms** will be the primary source of information in most experiments. They should be filled in with care and as comprehensively as possible, remembering that data analysis may be carried out by someone other than the individual who did the assessment, and may be carried out a number of years later when recollection of the assessment may be difficult. All data from the forms should be captured into a spreadsheet or database as soon as possible after they have been collected. By capturing data on separate sheets with the same format, first-level data checks can be carried out using comparative graphs.

**Photographs and videos** will be invaluable in later analysis. Cross references and details of when and where the photograph and videos were taken and what they illustrate must be captured on the evaluation form.





Data board

EP-PPTS/3/05/1/ver1 Proposal number

PPTS/3/05/1/1 Section number

ES-PPTS/05/1/ver1 Work plan number

CR-PPTS/05/1/ver1 Construction report

IR-PPTS/05/1/ver1 Interim/progress report

ER-PPTS/05/1/ver1 Experiment report Photographs should be stored electronically in a series of subdirectories linked to the monitoring dates. Care must be taken to ensure that the numbers on the photographs match those on the evaluation forms and that there will be no confusion when analyzing the data. The date, and if appropriate the time, that the photograph was take should be included in the file name. Key information can also be recorded on a data board in the photograph.

**Centralized numbering systems** provide a simplified means of tracking experiments statewide, and the documentation prepared from them. Numbers can be obtained from the Chief of the Office of Pavement Preservation. The following numbering systems are used:

- Experiment Proposal Register
- Experiment Register
- Report Number Register

The data collected from each evaluation should undergo a **first-level data check** by both the Project Engineer and the Database Manager. This will include, but not be limited to:

- A check that data does not fall outside predetermined minimum and maximum boundaries (e.g., a severity cannot exceed 5, percentage areas cannot exceed 100)
- A comparison with data collected from the previous monitoring exercise to check inconsistencies (e.g., rut depth less than previous)

**All projects need to be closed.** For a pavement preservation experiment, project closure will usually occur once the final report has been submitted and an implementation plan has been initiated by the Chief of the Office of Pavement Preservation.

#### 12. BIBLIOGRAPHY

1. California Department of Transportation Web site -

http://www.dot.ca.gov.

- Caltrans Safety Manual. 2000. Sacramento, CA: State of California Department of Transportation. http://www.dot.ca.gov/hq/opo/safety/safetymanual
- 3. **Construction Manual.** 2003. Sacramento, CA: State of California Department of Transportation.

(http://www.dot.ca.gov/hq/construc/manual2001/

- Distress Identification Manual for the Long term Pavement Performance Program (4<sup>th</sup> Edition). 2003. Washington, DC: Federal Highway Administration. (FHWA-RD-03-031).
- 5. www.tfhrc.gov/pavement/ltpp/reports/03031/03031.pdf
- Generic Experimental design for Product/strategy Evaluation -Crumb Rubber modified Materials. 2005. Sacramento, CA: State of California Department of Transportation. (www.dot.ca.gov/hg/esc/Translab/fpmlab/)
- 7. Guide to the Investigation and Remediation of Distress in Flexible Pavements.
- 8. Index of California Test Methods http://www.dot.ca.gov/hq/esc/ctms/
- Maintenance Manual. 2000. Sacramento, CA: State of California Department of Transportation. (http://www.dot.ca.gov/hq/maint/manual/).
- Maintenance Technical Advisory Guide (MTAG). 2003. Sacramento, CA: State of California Department of Transportation. (www.dot.ca.gov/hq/maint/mtag/)
- New Product Evaluation Guidelines. 1999. Sacramento, CA: State of California Department of Transportation. (www.dot.ca.gov/hq/esc/approved\_products\_list/NPGuidelines.html)
- 12. **Pavement Condition Survey Manual.** 2002. Sacramento, CA: State of California Department of Transportation.



# **APPENDIX A: CHECKLISTS**

Examples of the following checklists typically used in pavement preservation experiments are provided in this Appendix:

- Checklist 1: Justification for Study
- Checklist 2: Proposal for a Pavement Preservation Experiment
- Checklist 3: Project Planning
- Checklist 4: Experiment Work Plan Content
- Checklist 5: Experiment Work Plan Document
- Checklist 6: Experiment Initiation
- Checklist 7: Desktop Study
- Checklist 8: Site Selection
- Checklist 9: Site Layout and Marking
- Checklist 10: Preconstruction Assessment
- Checklist 11: Construction Assessment
- Checklist 12: Monitoring Preparation
- Checklist 13: Monitoring
- Checklist 14: Project Closure

	CHECKLIST - JUSTIFICATION FOR STUDY Checklist 1						
	Issue	Yes	No	Commen	ts		
1	Has similar research been done by any other individual/organization?						
2	Are the findings of previous studies applicable to Caltrans?						
3	Are the findings statistically valid?						
4	Will doing a similar study provide additional useful information to advance knowledge or enhance implementation by Caltrans?						
5	If the study is undertaken, will it be practical for Caltrans to adopt/implement the findings in practice?						
6							
7							
8							
9							
10							
11							
12							
	F	Recomn	nendat	ion			
Shou If no	Id the study proceed? , state why and what needs to be done to cont	tinue.			Y	es No	
Nam	e Sigr	nature		Date	Э		

C	CHECKLIST - PROPOSAL FOR A PAVEMENT PRESERVATION EXPERIMENT Checklist 2						
	Issue	Yes	No	Com	ments		
1	Is the purpose of the experiment clear?						
2	Was the background study sufficiently						
_	comprehensive to justify that the						
0	experiment is required?						
3	experiment justifiable in terms of potential						
	benefits to Caltrans?						
4	Are details on how the findings would be						
	implemented by Califans adequate?						
5	Is the work plan sufficiently comprehensive						
	such that statistically valid data will be						
6	Is the study timetable appropriate?						
Ũ							
/	and realistic? Have the cost of traffic						
	closures been included?						
8	If a proprietary additive/procedure is being						
	provided adequate?						
9	Have potential partners been identified?						
10	Has an individual/position accented						
10	responsibility for completing the study in						
	the proposed time frame?						
11	Has an individual/position accepted responsibility for implementing the findings						
	into Caltrans practice?						
12	Has the proposal been registered with the						
	Chief of Office of Pavement Preservation?						
13	Has a proposal number been issued?						
	F	Recomm	nondat	ion			
Is th	e proposal adequate?	leconn	nenual		Ye	es No	
lf no	, state why and what needs to be done to cont	inue				•	
Nam	le Sigr	ature			Date		

	CHECKLIST - PROJECT PLANNING MEETING Checklist 3						
	Issue	Yes	No	Com	ments		
1	Is the objective of the experiment clear?						
2	Have the implications of the findings from	n					
_	the background study been adequately						
2	established?						
3	test objective?						
4	Has a suitable control experiment for	n2					
	comparative purposes been agreed upor						
5	Has the location of the experiment been						
	decided?						
6	Have all the construction requirements						
	been identified?						
7	Has the instrumentation and equipment						
,	required to provide data for envisaged						
	outcome been identified?	-					
8	Has a monitoring program been drawn u	p?					
9	Has a monitoring procedure been agreed	d					
	to?						
10	Have failure and experiment completion						
	criteria been set?						
11	Has an apposited laboratory toot progra						
	been formulated?	4/11					
12	Have data collection, validation and						
	storage protocols been agreed upon?						
13	Have report formats and frequency been	1					
	defined?						
14	Have criteria been set for the						
	treatment/technology/procedure/product	to					
	be adopted as standard practice?						
15	Has a plan for implementing the treatme if successful been formulated?	nt					
16	Has consideration been given to repairin	g					
	the road after testing?						
17	Has responsibility for each of the above						
	been delegated and accepted?						
		Becomm	andat	ion			
Has	sufficient information been gathered to pro	epare an ex	perime	ent work plan?	Ye	es No	
lf no	, state why and what needs to be done to	continue.	•		L		
Nam	ie	Signature			Date		
			1				

	CHECKLIST - EXPERIMENT WORK PLAN CONTENT Checklist 4						
	Content		Yes	No	0	Comments	
1	Objective of the test						
2	Staffing and contact details						
3	Responsibility and reporting matrix						
	Report preparation						
	Report approval						
	<ul> <li>Health and safety</li> <li>Environment</li> </ul>						
	Environment     Data collection						
	Data validation						
	Data submission						
4	Experimental design, including details on	replicates					
	and controls	•					
5	Section detail						
	Section number						
	<ul> <li>Section details including district, count number, lane number and CPS apardii</li> </ul>	ty, route					
	Test panel position	nales					
	Pavement description						
	<ul> <li>Construction, rehabilitation or mainten</li> </ul>	ance					
	interventions required before testing ca	an begin					
	Checklists						
6	Instrumentation						
	<ul> <li>Inventory of instruments</li> </ul>						
	<ul> <li>Location and/or depth</li> </ul>						
	Calibration						
	Measurement specifications						
	<ul> <li>Data collection requirements including and leastion of points and conditions up</li> </ul>	number					
	which measurements will be recorded	linger					
	Checklists						
7	Evaluation program						
	Evaluation detail						
	<ul> <li>Protocols/methods/criteria to be follow</li> </ul>	red					
	<ul> <li>Failure criteria definition</li> </ul>						
	<ul> <li>Associated laboratory testing</li> </ul>						
	Checklists						
8	Data collection, validation, and storage						
	Start date						
	Frequency of data collection						
	<ul> <li>Data validation (visual, comparison with provide the second secon</li></ul>	th					
	previous measurement, within predefin	nea					
	<ul> <li>Data transfer to Database Manager (til)</li> </ul>	mina					
	medium)						
	Criteria to be met for experiment comp	oletion					
	Checklists						
9	Reports						
10	General notes	Decement	and atta	Ļ			
Haa	sufficient information been included in the	experiment	work pl	11 2n?		Va	e No
If no	state why and what needs to be done to c	continue	work p	ant		re	
Nam	ie S	Signature				Date	

	CHECKLIST - EXPERIME		( PLAI	N REF	PORT		Checklist 5	
	Content		Yes	No		Comments		
4 T:+				_				
1 Π 2 Δn	ne page ?							
3 Be	evision notes page?							
4 Ta	ble of contents?							
5 Ch	apter 1: Objective of the test							
6 Ch	apter 2: Staffing and contact details							
7 Ch	apter 3: Responsibility and reporting m	natrix						
8 Ch	apter 4: Experimental design							
9 Ch	napter 4: Section detail							
10 Ch	napter 5: Instrumentation							
11 Ch	napter 6: Monitoring program							
12 Ch	napter 7: Data collection, validation, and	d storage						
13 Ch	apter 8: Reports							
14 Ch	apter 9: General notes							
15 Ap	pendices: Checklists and forms							
16 Re	eports							
17 Ge	eneral notes							
	Issue		Yes	No		Comments		
1 Do	es the work plan have a number?							
2 Ha	as the work plan been submitted and ap	proved by						
the	e Chief of the Office of Pavement Prese	rvation?						
3 Ha	ave copies been distributed?							
4 Ha	ave instructions for revisions been distrik	outed?						
	Recommendation							
Has the	Has the experiment work plan phase of the experiment been satisfactorily completed?							
If no, st	ate why and what needs to be done to o	continue.						
	Natao							
		NO	165					
Name		Signature				Date		
		-						

	CHECKLIST - EXPERIMENT INITIATION Checklist 6							
	General issues	Yes	No	Comr	ments			
1	Has the Project Champion given written approval to proceed with the experiment?							
2	Has a copy of the approval been added to the Project File?							
3	Has an experiment number been issued by the Chief of the Office of Pavement Preservation?							
4	Has a project team been assembled?							
5	Has the project team accepted responsibilities as assigned in the experiment work plan?							
6	Have all necessary arrangements been made to proceed with the experiment?							
7								
8								
9								
10								
11								
12								
	F	Recomn	nendat	ion				
If no	the experiment proceed? , state why and what needs to be done to con	tinue.			<u>Ye</u>	es No		
Nam	le Sign	nature			Date			

	CHECKLIST - SITE SELECTION DESKTOP STUDY Checklist 7								
	General issues	Yes	No	Comments					
1	Do the identified roads and sections meet the requirements of the experiment work plan?								
2	Can the experiment be incorporated into a planned pavement preservation activity on the proposed road?								
3	If a planned activity, can the planned treatments be accommodated in the operation?								
4	If a planned activity, can the planned pavement preservation treatment on the selected section be used as a control?								
5	Is the planned operation long enough to accommodate the experiments?								
6	Is the alignment uniform?								
7	Is the planned operation long enough to accommodate replicate sections?								
8	Are there any potential problems envisaged with later monitoring activities (e.g., road closures)?								
9	Are there constraints outside the Experiment Work Plan that could influence the use of the site (e.g., safety)?								
10	Is appropriate construction equipment available?								
11	Are there appropriately trained personnel to do the treatments?								
12	Can the contractual arrangements be modified to accommodate the experiment?								
		Recomm	nendat	ion	1 1				
If no	s the proposed site meet the requirements of , state why and what needs to be done to co	the expendent	erimen	t work plan?	Yes No				
Nam	e Sig	Inature		Date					

CHECKLIST - SITE SELECTION Checklist 8												
	General issues	Yes	No	Com	ments							
1	Is the proposed section representative of the issue being investigated?											
2	Is the proposed section conveniently located for monitoring and demonstration purposes?											
3	Will any results obtained from this proposed section be representative of other roads with similar conditions?											
4	Are individual sections within the proposed experiment similar in terms of alignment, structure and condition?											
5	Will the establishment of the proposed section pose a safety hazard to road users?											
6	Will the establishment of the proposed section pose a safety hazard to persons undertaking monitoring evaluations?											
7	Will the road on which the proposed section is planned be maintained or rehabilitated within the monitoring period?											
8	Can planned maintenance be included as part of the evaluation?											
9	If planned maintenance is not part of the evaluation, can steps be taken to ensure that the experiment is not maintained?											
10	Is the proposed section located as close as possible to a traffic counting/weigh-in- motion station?	\$										
11	Can the proposed section be tested to 'failure' and then repaired without significant impacts to the road user?											
12												
_		Recomm	nendat	ion								
lf no	, state why and what needs to be done to co	ntinue.	erimen	t work plan?	Yes No							
Nam	Si	gnature			Date							

	CHECKLIST - SITE LA	YOUT A	ND M	ARKING	Checklist 9
	General issues	Yes	No	Comments	; ;
1	Were product suppliers present?				
2	Were appropriate criteria used to identify				
	representative sections?				
3	Are the selected sites sufficiently uniform?				
1	Are there any attributes that may adversely				
-	influence the performance of the				
_	treatment?				
5	Can all necessary safety procedures be implemented/followed?				
	···· P·····				
6	Can all necessary environmental				
	procedures be implemented/followed?				
7	Are the product suppliers satisfied that their	r			
	products will be fairly evaluated?				
8	Has the section been marked according to				
	the experiment work plan?				
9	Were GPS coordinates taken?				
Ũ					
10	Have instruments been installed and				
10	calibrated according to the manufacturer's				
	specifications?				
11	Have arrangements been made for the collection of weather data?				
12	Has an experiment map been drawn?				
13	Has an experiment number been				
	allocated?				
14	Have signs been erected?				
15	Has experiment register been updated?				
16	Liss construction been ashedulad?				
01	has construction been scheduled?				
			L		
Doe	s the proposed site meet the requirements of	the exp	nendat erimen	ion t work plan?	Yes No
If no	, state why and what needs to be done to co	ntinue.		<b>P</b>	
Nam	le Sig	gnature		Date	

	CHECKLIST - PRE-CON	STRUCTIO	ON ASSESSMENT Check								
	General issues	Yes	No	Com	iments						
1	Were correct safety precautions taken?										
2	Was the traffic closure acceptable?										
3	Are the selected sites sufficiently uniform	n?									
4	Were product suppliers present?										
5	Was a comprehensive visual assessmer	nt									
	undertaken?										
6	Was the prescribed form used to capture	e									
	data?										
7	Was any destructive testing carried out.										
	and if yes, was the damage appropriatel	у									
8	repaired? Are the experiment signs intact?										
9	Is the instrumentation installed during										
	experiment establishment functioning										
10	correctly?	NV.									
10	influence the performance of the	, i y									
11	experiment?	2									
''	Thas the toau been adequately prepared	:									
10											
12	construction can proceed?										
13											
14											
15											
Sho	uld construction of the experiment process	Recomm	nendat	ion	Yes No						
If no	, state why and what needs to be done to	continue.									
Nam	ie	Signature			Date						

	CHECKLIST - CONST	ASSE	SESSMENT Checklist 11							
	General issues	Yes	No	Com	ments					
1	Was the entire process systematically documented?									
2	Were all deviations from the planned process justified and/or explained?									
3	Have the potential influence of the deviations on the experiment performant been quantified?	ce								
4	Were the binder, aggregate and/or prem characteristics documented?	ix								
5	Was the equipment inspected and condition documented?									
6	Was the equipment correctly calibrated?									
7	Was the area of distress adequately prepared?									
8	Was the surfacing/patch/crack seal adequately compacted?									
9	Were establishment, application and demobilization times recorded?									
10	Were appropriate quality control procedures followed?									
11	Was the treatment uniform throughout the experiment?	ie								
12	Was wastage documented?									
13	Were any unanticipated problems encountered and how were they dealt with?									
14	What procedures can be implemented to improve the process?	)								
15	Were the required measurements taken the specified intervals?	at								
16	Were the required samples taken at the specified intervals?									
17	Were instruments installed as specified?									
18	Were the product suppliers satisfied with the experiment?									
		Recomm	nendat	ion						
Was	the experiment satisfactorily constructed	?			Ye	es No				
Nam		Signature			Date					

	CHECKLIST - MONITO	REPA	PARATION Checklist 12								
	General issues	Yes	No	Comme	ents						
1	Have all notifications been made?										
2	Have road closures and traffic control										
	arrangements been made?										
3	Has assessor training and calibration been										
	completed?										
4	Are section maps, previous monitoring										
•	forms, blank forms, visual assessment										
_	guide, and experiment work plan packed?										
5	Is equipment packed? (Camera, geo pick, straight edge, wedge, tape measure, GPS,										
	DCP, moisture cans, pick, spade, etc.)										
6	Is safety equipment packed? (Protective										
	ciotining, vests, inst-aid, water, etc.)										
7	Is the equipment correctly calibrated?										
	(Nuclear gage, DCP weight and cones,										
8	Have other equipment been arranged?										
	(e.g., FWD and profiler, etc.)										
9											
5											
10											
10											
11											
12											
		Recomm	nendat	ion							
Can	monitoring proceed?				Ye	es No					
11 110	, state why and what needs to be done to cor	illinue.									
Nar		noturo			) et e						
nan	Sig	nature			ale						

	CHECKLIST	RING	IG Checklist 1						
	General issues	Yes	No	Comments					
1	Was the experiment monitored according to the requirements of the experiment wo plan?	rk							
2	Was the standard prescribed form used? not, has all relevant information been captured?	lf							
3	Were all cells on the form completed?								
4	Was the assessment compared to the previous assessment?								
5	Were any significant changes since the previous monitoring accounted for?								
6	Were the required photographs taken?								
7	Were the required physical measurement taken?	S							
8	Were the required samples taken?								
9	Were the samples logged?								
10	Were the samples delivered and instructions for testing submitted?								
11	Have the data and photographs been captured in a spreadsheet or database?								
12	Have all forms been added to the project file?								
13									
14									
15									
		Recomme	ndatio	n					
Was If no	the monitoring exercise successfully comp , state why and what needs to be done to c	oleted? continue.			Yes No				
Nam	ie (	Signature		Date					

	CHECKLIST - PROJECT CLOSURE Checklist 1												
	General issues	Yes	No	Comments	1								
1	Has the monitoring been completed in terms of the requirements of the experiment work plan?												
2	Have the objectives of the experiment bee met?	en											
3	Is termination of the project justified?												
4	Have all reports as required in the experiment work plan been written?												
5	Have all the objectives of the experiment as detailed in the work plan been addressed?												
6	Have all reports had an independent technical review?												
7	Have all reports been logged with the Chie of the Office of Pavement Preservation an numbered in the central register?	ef d											
8	Have the required steps been taken to have the findings implemented?												
9	Have the findings been presented to relevant Caltrans departments and if applicable, published?												
10	Has all data been captured in the databas and backed up?	e											
11	Has the project file been closed and archived?												
12	Have materials samples been disposed of	?											
13	Have signs, markings and instrumentation been removed from the site?												
14	Have all registers been updated by the Chief of the Office of Pavement Preservation?												
15	Have all team members and other interested and affected parties been notified?												
		Recomme	ndatio	n									
Was If no	the project successfully completed? , state why and what needs to be done to co	omplete it.			Yes No								
Nam	ie S	ignature		Date									



# **APPENDIX B: DATA COLLECTION FORMS**

Examples of the following forms typically used for the monitoring of pavement preservation experiments are provided in this Appendix:

- Form 1: Visual Assessment Form used for Chip Seal Evaluation (alternative to Pavement Condition Survey standard form)
- Form 2: Profile Assessment
- Form 3: Construction Assessment form for Chip Seal Application
- Form 4: Materials Inventory
- Form 5: Project Site Report
- Form 6: Section Sketch
- Form 7: Core Log
- Form 8: Test Pit Sketch
- Form 9: Log for Surfacing Layers
- Form 10: Log for Granular and Stabilized Base
- Form 11: Photographs
- Form 12: Density and Moisture Content
- Form 13: DCP

PAV	EMENT PRESERV	ATION EXPE	RIMENT CO	ONSTRI	JCTION A	ASSESS	SMENT FO	RM	Form 1	
Secti	on No	Location			Date		Evalua	itor		
Expe	riment description									
Weat	her conditions									
Dates	/Times	Establi	shment				Road clo	sure		
		Road C	pening				Demobiliz	ation		
Surfa	ce preparation									
Ś	Distributor									
tion	Chip spreader									
pect	Haul trucks									
ins	Rollers									
ient I cal	Broom									
anc										
Equ										
	Source/type									
	Application rate			-						7
der	Total applied			-						lote
Bi	Temperature			-						S
	Samples			-						
	Source/type									
te	Application rate			-						7
ega	Total applied			_						lote
Aggı	Temperature			-						S
	Samples			-						
c	Roller									
ctio	Passes			-						No
npa				-						tes
Col				-						
_										
ning										Not
00,										les
ā										
Notes	5						Photos/v	ideo	·	

PAVEMENT PRESERVATION EXPERIMENT VISUAL ASSESS											SSMENT FORM Form2(a)						
Section No				Loc	atio	n					Da	te		Evalua	ntor		
Surfacing type		<u> </u>					S	Surfa	ncing	g as	ses	sme	nt				
		V	arvi	na	1	Fino		F	- M		Mod	ium	M - C				
Veide			ai yi	ng		long					E						
Volus		V	aryı			vone					. rew		F - M	IVIC			
			Slig	De ht	gree S	e Seve	re			xte	nt 8	0	Leng	th		Width	Panels
Mechanical failure		0	1	2	3	4	5	1	2	3	4	5					
Other failure		0	1	2	3	4	5	1	2	3	4	5					
Bleeding/flushing		0	1	2	3	4	5	1	2	3	4	5	Narrow	Wi	de	Position	
Surface cracks		0	1	2	3	4	5	1	2	3	4	5					
Binder condition		0	1	2	3	4	5	1	2	3	4	5	Active	Sta	ble	Position	
Aggregate loss		0	1	2	3	4	5	1	2	3	4	5					
		<u> </u>		Do	<u>aro</u> ,		S	truc	tura	l as	ses	sme	nt Norrow		ida		
			Slig	ht	gree	e Seve	re		<5 ⊑	xte		)	(% area)	(% a	area)	Position	Panels
Cracks - block		0	1	2	3	4	5	1	2	3	4	5					
Cracks - longitudin	0	1	2	3	4	5	1	2	3	4	5						
Cracks transverse	0	1	2	3	4	5	1	2	3	4	5						
Cracks - crocodile	0	1	2	3	4	5	1	2	3	4	5						
Cracks - parabolic	0	1	2	3	4	5	1	2	3	4	5						
Pumping		0	1	2	3	4	5	1	2	3	4	5					
Rutting		0	1	2	3	4	5	1	2	3	4	5					
Undulation/settlem	ent	0	1	2	3	4	5	1	2	3	4	5					
Edgebreak		0	1	2	3	4	5	1	2	3	4	5	Number	Dian	neter		
Potholes		0	1	2	3	4	5	1	2	3	4	5					
Delamination		0	1	2	3	4	5	1	2	3	4	5					
Patching		0	1	2	2	4	5	1	2	2	4	5	Small	Mec	lium	Large	Panels
Patching			<u> </u>	2	3	4	5		2	3	4	5					
		Dec	aree	)			г	Inci	IONa	ai as	sses	sme	Influencin	g facto	rs		
	Go	od	, 	Pool	r					-				-		-	
Riding quality	1	2 :	3	4	5	Poth	oles	S	F	Patc	hing	J	Undula	ition	C	orrugation	Ruts
Skid resistance	1	2,	3	4	5	ыее	ainę	3	P	OIIS	sning	3					
Surface urainage	<u>'</u>	2	3   v	4	5												
Side drainage	•		<u></u>														
NOTES																	

PAVEMENT PRESERVATION EXPERIMENT VISUA	AL A	ASSESSMENT FORM Form2(b)								
Sample details		Photos	3							
		******								
		*****								
		***************************************								
		***************************************								
		*****								
		*****								
		*****								
		******								

					Transverse																			Se				
	Width	Max Rut	Panel 5		Width	Max Rut	Panel 4		Width	Max Rut	Panel 3		Width	Max Rut	Panel 2		Width	Max Rut	Panel 1		Width	Max rut	Panel A	ction No	PAVEME			
	Lane	Center			Lane	Center			Lane	Center			Lane	Center			Lane	Center			Lane	Center			TN			
2.1			1.9	2.1			1.9	2.1			1.9	2.1			1.9	2.1			1.9	2.1			1.9		PRE			
2.2			1.8	2.2			1.8	2.2			1.8	2.2			1.8	2.2			1.8	2.2			1.8		SER			
2.3			1.7	2.3			1.7	2.3			1.7	2.3			1.7	2.3			1.7	2.3			1.7		VAT			
2.4			1.6	2.4			1.6	2.4			1.6	2.4			1.6	2.4			1.6	2.4			1.6	Pane	ONE			
2.5			1.5	2.5			1.5	2.5			1.5	2.5			1.5	2.5			1.5	2.5			1.5		EXPE			
2.6			1.4	2.6			1.4	2.6			1.4	2.6			1.4	2.6			1.4	2.6			1.4		RIME			
2.7			1.3	2.7			1.3	2.7			1.3	2.7			1.3	2.7			1.3	2.7			1.3	01	TNE			
2.8			1.2	2.8			1.2	2.8			1.2	2.8			1.2	2.8			1.2	2.8			1.2	Dat	PROF			
2.9			1.1	2.9			1.1	2.9			1.1	2.9			1.1	2.9			1.1	2.9			1.1	œ	ILE.			
3.0			1.0	3.0			1.0	3.0			1.0	3.0			1.0	3.0			1.0	3.0			1.0	ņ	ASSI			
3.1			0.9	3.1			0.9	3.1			0.9	3.1			0.9	3.1			0.9	3.1			0.9	valua	ISS			
3.2			0.8	3.2			0.8	3.2			0.8	3.2			0.8	3.2			0.8	3.2			0.8	tor	NENT			
3.3			0.7	3.3			0.7	3.3			0.7	3.3			0.7	3.3			0.7	3.3			0.7		FOF			
3.4			0.6	3.4			0.6	3.4			0.6	3.4			0.6	3.4			0.6	3.4			0.6		R			
3.5			0.5	3.5			0.5	3.5			0.5	3.5			0.5	3.5			0.5	3.5			0.5					
3.6			0.4	3.6			0.4	3.6			0.4	3.6			0.4	3.6			0.4	3.6			0.4					
3.7			0.3	3.7			0.3	3.7			0.3	3.7			0.3	3.7			0.3	3.7			0.3		For			
3.8			0.2	3.8			0.2	3.8			0.2	3.8			0.2	3.8			0.2	3.8			0.2		m 3(a			
3.9			0.1	3.9			0.1	3.9			0.1	3.9			0.1	3.9			0.1	3.9			0.1		е)			
CL			RE	CL			RE	CL			RE	CL			RE	CL			RE	CL			RE					
	Lon	ıg													Trans	verse		•										Se
------------	-------	-------	----------	-----	-------	---------	-------------	-----	-------	---------	---------	-----	-------	---------	---------	-------	-------	---------	---------	-----	-------	---------	---------	-----	-------	---------	---------	----------
Lane cente	Inner	Outer	Position		Width	Max Rut	Panel 10		Width	Max Rut	Panel 9		Width	Max Rut	Panel 8		Width	Max Rut	Panel 7		Width	Max Rut	Panel 6		Width	Max Rut	Panel B	ction No
ər					Lane	Center			Lane	Center			Lane	Center			Lane	Center			Lane	Center			Lane	Center		
				2.1			1.9	2.1			1.9	2.1			1.9	2.1			1.9	2.1			1.9	2.1			1.9	
				2.2			1.8	2.2			1.8	2.2			1.8	2.2			1.8	2.2			1.8	2.2			1.8	
				2.3			1.7	2.3			1.7	2.3			1.7	2.3			1.7	2.3			1.7	2.3			1.7	
			N	2.4			1.6	2.4			1.6	2.4			1.6	2.4			1.6	2.4			1.6	2.4			1.6	
				2.5			1.5	2.5			1.5	2.5			1.5	2.5			1.5	2.5			1.5	2.5			1.5	anel
			ω	2.6			1.4	2.6			1.4	2.6			1.4	2.6			1.4	2.6			1.4	2.6			1.4	
				2.7			1.3	2.7			1.3	2.7			1.3	2.7			1.3	2.7			1.3	2.7			1.3	6 - 10
			4	2.8			1.2	2.8			1.2	2.8			1.2	2.8			1.2	2.8			1.2	2.8			1.2	L
				2.9			1.1	2.9			1.1	2.9			1.1	2.9			1.1	2.9			1.1	2.9			1.1	
			сı	3.0			1.0	3.0			1.0	3.0			1.0	3.0			1.0	3.0			1.0	3.0			1.0	
				3.1			0.9	3.1			0.9	3.1			0.9	3.1			0.9	3.1			0.9	3.1			0.9	
			6	3.2			0.8	3.2			0.8	3.2			0.8	3.2			0.8	3.2			0.8	3.2			0.8	
				3.3			0.7	3.3			0.7	3.3			0.7	3.3			0.7	3.3			0.7	3.3			0.7	
			7	3.4			0.6	3.4			0.6	3.4			0.6	3.4			0.6	3.4			0.6	3.4			0.6	
				3.5			0.5	3.5			0.5	3.5			0.5	3.5			0.5	3.5			0.5	3.5			0.5	
			ω	3.6			0.4	3.6			0.4	3.6			0.4	3.6			0.4	3.6			0.4	3.6			0.4	
				3.7			0.3	3.7			0.3	3.7			0.3	3.7			0.3	3.7			0.3	3.7			0.3	
			9	3.8			0.2	3.8			0.2	3.8			0.2	3.8			0.2	3.8			0.2	3.8			0.2	orm
				3.9			0.1	3.9			0.1	3.9			0.1	3.9			0.1	3.9			0.1	3.9			0.1	3(b)
			0	CL			RE	CL			RE	CL			RE	CL			RE	CL			RE	CL			RE	

PAVEMENT PRESERVATION EXPERIMENT - MATERIALS INVENTORY										
Section No		Operator			Date					
Sample Number	Sample location	Sample size	Sample type	Material type and code	Sample condition	Program of work				
			***************************************							
nts										
Jme										
Con										
1819111010101010101010101010										
Responsibl	e person									
				Sign						

PAVEMENT PRE	ESER\	ATION EXPERIMENT INV	/EST	IGATION - PROJE	CT SITE	REPORT	Form 5
Section No				Date			
Start time				Completion time			
Responsibility				Crew chief			
Head driller				Crew size			
Traffic control				Repair			
Weather							
Equipment							
Description of work and comments							
		Description		Shipped to	Sh	ipped by	Date
-							
Samples							
				***************************************			
ľ							
		Equipment		Traffic		Othe	er
Site problems							
			Fo	rms	1		
Sketch		Materials inventory		Core log		Pit asses	sment
DCP		Density/moisture		List of photograp	hs		
Pit reinstated				Site cleaned			
Responsible per sign	son			Date			

	PAVEMENT PRESERVATION EXPERIMENT INVESTIGATION - SKETCH Form 6											
Section	No		Date		Evaluator							
	E	xperimental section	plan and lo	ocation of test pit(s	s), core points a	nd testing loc	ations					
				Centerline								
tart												
S												
				Shoulder								
Reference	e	Activity		De	scription and re	ason						

PA	VEME	NT PRE	SERVATION E	XPERIMENT I	<b>NVESTIGATION - CORE</b>	LOG	Form 7
Section No					Date		
Evaluator					Operator		
Core hole No	)				Sketch		
Equipment							
Core size							
Coolant							
Offset							
Reason for c	ore						
	Core	a drilled	Core				Material
Depth	(1	mm)	recovered	Sample No	Layer thickness an	d description	code
	•••••••						
							****
	•••••••						
Comr	nents						•

PAVEMENT PRESERVATION EXPERIMENT INVESTIGATION - TEST PIT SKETCH									
Section	n No:		Profiled by:		C	Date:			
		Zone 5	Zone 4	Zone 3	Zone 2		Zone 1		
	(IW	T to centerline)	(IWT)	(Between tracks)	(OWT)	(Sł	noulder to OWT)		
								_	
Γ									
l L								]	

	PAVEMENT PRESERVATION EXPERIMENT INVESTIGATION - WEARING COURSE LAYERS Form 9												
Section	n No:	Profiled by:							Date:				
Depth	Descriptor	Zone 1		Zor	ne 2	Zon	e 3	Zo	one 4	2	Zone 5	Sample	
(mm)		(Shoulder to	OWT)	(O)	WT)	(Between	tracks)	(1	WT)	(IWT to	o centerline)	No	
to													
to				*******			*****						
to													
to													
to								****					
to													
Interlay	/er bond												
			<b>D</b>										
	Cracks		Descriptio	on .									
Checkl	Butting		Heaving		Blee	edina		Raveling					
	Interface	e bond	Moisture	at interface	Lave	er definition		Pumping					
01					,								
Other													

	PAVEMENT PRESERVATION EXPERIMENT INVESTIGATION - LOG FOR GRAVEL AND STABILIZED LAYERS Form 10											
Section	No	Profiled by:					Date:					
Depth	Descriptor	Moisture	Color	Consistency	Structure	Size		Other	Sample			
(mm)												
to												
to												
							••••					
to												
to												
to												
							••••					
to												
Surface	e/laver bond											
	···· <b>·</b>											
	Crac	cks	Description									
Checkl	ist Rutti	ing	Pumping	In	terface bond	Moisture at	t interface	Layer definition				
	Carb	oonation										
Other				·····								
Other												

PAVEMENT PRESERVATION EXPERIMENT INVESTIGATION - PHOTOGRAPHS For								
Section No	D			Date				
Evaluator								
Photo				<b>.</b>		Storage		
number		Location		Description		disc		

PAVEMENT PRESERVATION EXPERIMENT DENSITY & MOISTURE CONTENT Form 12										
Section No				Date		Evalua	ator			
Calibration		Prv	Std	Std	Std	Calibr	ated by			
Std MC						Calibr	ation date			
Std wet densit	V									
	Probe	Input	Actual	W	/et	Drv	MC	Notes		
	24	200	600							
	22	200	550							
	20	200	500							
	18	200	450							
A	16	200	400							
lər	14	200	350							
ar	12	200	300							
ш	10	200	250							
	8	200	200							
	6	150	150							
	4	100	100							
	2	50	50							
	24	200	600							
	22	200	550							
	20	200	500							
	10	200	450				+			
	18	200	450							
B	16	200	400							
e	14	200	350							
an	12	200	300							
Ċ.	10	200	250							
	8	200	200							
	6	150	150							
	0	100	100							
	4	100	100							
	2	50	50							
	24	200	600							
	22	200	550							
	20	200	500							
	18	200	450							
	16	200	400							
0	14	200	350							
ne	10	200	200							
Ра	12	200	050							
	10	200	250							
	8	200	200							
	6	150	150							
	4	100	100							
	2	50	50							
				Gravim	etric mo	isture content	•			
	Samp	le T	ïn No	Mois	sture	Actual dry		Notes		
	depth	ו ו		con	tent	density				
				-		-				
A										
st										
μ										
8							_			
st										
Ĕ										
O										
st										
Te										
Validated by	/					Signaturo				
vanualeu by						Signature				

PA	VEME	ENT PF	RESERVATI	ON EXPE	RIMENT	DCP RECOR	DING SHEE	Г	Form 13
Section	No			Panel		Date	Оре	erator	
Position	ו A			Positi	on B		Posi	tion C	
0		1		0			0		
5	205		405	5	205	405	5	205	405
10	210		410	10	210	410	10	210	410
15	215		415	15	215	415	15	215	415
20	220		420	20	220	420	20	220	420
25	225		425	25	225	425	25	225	425
30	230		430	30	230	430	30	230	430
35	235		435	35	235	435	35	235	435
40	240		440	40	240	440	40	240	440
45	245		445	45	245	445	45	245	445
50	250		450	50	250	450	50	250	450
55	255		455	55	255	455	55	255	455
60	260		460	60	260	460	60	260	460
65	265		465	65	265	465	65	265	465
70	270		470	70	270	470	70	270	470
75	275		475	75	275	475	75	275	475
80	280		480	80	280	480	80	280	480
85	285		485	85	285	485	85	285	485
90	290		490	90	290	490	90	290	490
95	295		495	95	295	495	95	295	495
100	300		500	100	300	500	100	300	500
105	305		505	105	305	505	105	305	505
110	310		510	110	310	510	110	310	510
115	315		515	115	315	515	115	315	515
120	320		520	120	320	520	120	320	520
125	325		525	125	325	525	125	325	525
130	330		530	130	330	530	130	330	530
135	335		535	135	335	535	135	335	535
140	340		540	140	340	540	140	340	540
145	345		545	145	345	545	145	345	545
150	350		550	150	350	550	150	350	550
155	355		555	155	355	555	155	355	555
160	360		560	160	360	560	160	360	560
165	365		565	165	365	565	165	365	565
170	370		570	170	303	570	170	303	570
175	275		575	175	275	575	175	275	575
180	200		580	175	313	500	100	212	580
100	300		505	100	300	56U	100	300	500
100	303		500	100	305	202	100	300	505
190	390		595	105	390	590	190	390	590
195	395		595	195	395	595	195	395	595
200	400		600	200	400	600	200	400	600
Validated by				Sign	ature				